



European bus projects – CHIC, High V.Lo City, HyTransit and 3Emotion

Emerging results

FCH JU programme review – Nov 2016

Ben Madden – Element Energy



- Introduction
- Project status
- Emerging results – achievements and issues
- Conclusions
- Next steps – a larger deployment

The CHIC project is the first of a number of European bus demonstrations - 83 FC buses will soon be in operation



→ **83** fuel cell buses in operation or about to start operation

Current EU-funded fuel cell bus projects

● CHIC


- ✓ Bolzano – 5 FC buses
- ✓ Aargau – 5 FC buses
- ✓ London – 8 FC buses
- ✓ Milan – 3 FC buses
- ✓ Oslo – 5 FC buses
- ✓ Cologne* – 4 FC buses
- ✓ Hamburg* – 6 FC buses

● High V.LO-City (operation start planned for 2015)

- ✓ Liguria – 5 FC buses
- ✓ Antwerp – 5 FC buses
- ✓ Aberdeen – 4 FC buses

● HyTransit (operation start planned for 2015)

- ✓ Aberdeen – 6 FC buses



Current EU-funded fuel cell bus projects

● 3Emotion (operation start planned for 2016/2017)

- ✓ Cherbourg – 5 FC buses
- ✓ Rotterdam – 4 FC buses
- ✓ South Holland – 2 FC buses
- ✓ London – 2 FC buses
- ✓ Flanders – 3 FC buses
- ✓ Rome – 5 FC buses

Current national/regional-funded fuel cell bus projects:

- ✓ Karlsruhe * – 2 FC buses
- ✓ Stuttgart * – 4 FC buses


Legend:

- CHIC countries
- ✓ In operation
- ✓ Planned for operation
- * Co-financed by regional/national funding sources

The various projects are in different stages of completion



Total number of buses in Europe



Phase 1 cities – the EvoBus buses



Fuel cell bus in Milan (3 buses in total)



Fuel cell Postbus in Aarau (5 buses in total)



Fuel cell buses in Bozen/Bolzano (5 buses in total)

Phase 0 and Phase 1 cities – the Van Hool buses



Fuel cell buses in Oslo (5 buses in total)



Fuel cell bus in Cologne (2 buses in total)

Phase 1 cities – the Wrightbus buses in London



Fuel cell buses in London (8 in total)

The Solaris buses in Hamburg



Hamburg, Germany (2 buses in total)

Van Hool buses through High.V Lo City, HyTransit and 3EMotion



Aberdeen (10 buses in total) – HyTransit and High V. Lo City



Antwerp (5 buses in total) – High V. Lo City








... with more buses to come...

Phase 1: 5 high throughput, 350bar stations

About 380 tonnes of H₂ dispensed (to end Sept 2016)






| City | Picture | HRS/H ₂ Producer | Operation start | Type of HRS / source of H ₂ | Nber of fillings | Kg H ₂ refuelled |
|---------------|---|-----------------------------|-----------------|---|------------------|-----------------------------|
| Aargau |  | Carbagas (Air Liquide) | 2012 | Onsite electrolyser - 100% H ₂ from RES (hydropower, solar & wind energy, biomass) (+ trailer delivery as backup) | 7,364 | 103,769 |
| Bozen |  | Linde | 2014 | Onsite electrolyser - 100% H ₂ from RES (mix of hydropower, solar and wind energy) (+ trailer delivery as backup) | 2,627 | 48,027 |
| London |  | Air Products | 2010 | Trailer delivery of gaseous H ₂ (SMR) | 7,997 | 133,949 |
| Milan |  | Linde | 2013 | Onsite electrolyser from the electricity grid (mix of grid, CHP, solar energy) (+ trailer delivery as backup) | 1,610 | 20,709 |
| Oslo |  | Air Liquide | 2012 | Onsite electrolyser: 100% H ₂ from RES (hydro power) (+ trailer delivery as backup) | 3,619 | 73,715 |

SMR= Steam Methane Reforming - RES: Renewable Energy Sources; CHP: Combined Heat-and-Power

Phase 0: 3 high throughput, 350bar stations

Some 650 tonnes of H₂ dispensed (to end March 2016)



| City | Photo | HRS/H ₂ producer | Operation start | Type of HRS / source of H ₂ | Nber of fillings | Kg H ₂ refuelled |
|----------|---|-----------------------------|-----------------|---|------------------|-----------------------------|
| Cologne |  | Air products | 2011 | Trailer delivery of gaseous H ₂ by-product sourced nearby (chlor alkali electrolysis) | 1,642 | 22,235 |
| Hamburg |  | Linde | 2012 | Onsite electrolyser - H ₂ from RES (+ trailer delivery as backup) | 2,220 | 36,750 |
| Whistler |  | Air Liquide Canada | 2009 | Liquid H ₂ generated from hydro-electric power in Quebec, delivered to the buses in gaseous form | 23,671 | 591,590 |

Stations in Aberdeen (HyTransit) and Antwerp (High V. Lo City)



Aberdeen (on-site electrolysis)



Solvay (bi-product hydrogen)

- Introduction
- Project status
- Emerging results – achievements and issues
- Conclusions
- Resolving the cost problems - Joint procurement project
- Resolving the challenge of larger stations - NewBusFuel

Overall project snapshot: all technical targets have been achieved (data from end Sept 2016)




| Parameter | Project total (incl. ICE buses in Berlin) | Phase 1 cities | Project goal for the Phase 1 cities |
|-------------------------------------|---|------------------|-------------------------------------|
| Total distance travelled [km] | 9,626,116 | 3,991,056 | 2,750,000 |
| Total hours on FC system [h] | 519,498 | 269,394 | 160,000 |
| Average FC runtime per bus [h] | 6,820 | 6,690 | 6,000 |
| Replacement of diesel fuel [litres] | 4,469,043 | 1,633,990 | 500,000 |
| Total H2 refueled [kg] | 1,256,492 | 380,168 | <i>No target</i> |

→ Over 8 million kilometers driven up to now

→ Over 4 million litre of diesel saved so far

¹ and ² Figures do not include the ICE buses in Berlin

London buses – FC durability



Bus mileage (HyTransit and High V.Lo City)

| Site | Total km driven | Date |
|--------------------------------|-----------------|------------|
| HyTransit | | |
| Aberdeen | 460 991 | 26/09/2016 |
| | | |
| High V.LO-City | | |
| Aberdeen | 246 092 | 01/10/2016 |
| Antwerp | 124 056 | 19/08/2016 |
| | | |
| Total High V.LO-City | 370 148 | |
| Total both projects | 831 139 | |
| Total Aberdeen 10 buses | 707 083 | |

- Introduction
- Project status
- Emerging results – achievements and issues
- Conclusions
- Resolving the cost problems - Joint procurement project
- Resolving the challenge of larger stations - NewBusFuel

- Operating range can meet the demand of bus operators, with up to 400 km demonstrated, and 20h of service/day;
- the fuel cell bus offers a **flexibility of service** equivalent to a diesel bus and fits well into the Bus Rapid Transit concept

| City | Range ¹ | Daily duty ² |
|-----------------------|-------------------------|-------------------------|
| Aarau | 180 - 250 km | 18-20 hours |
| Bolzano | 220-250 km | 12 hours |
| Cologne | 350 km | 12-16 hours |
| Hamburg | 400 km | 8 – 16 hours |
| London | 250 - 300 km | 16-18 hours |
| Milano | 170 km | Up to 16 hours |
| Oslo | 200 - 290 km (seasonal) | Up to 17 hours |
| Whistler ³ | 366 – 467 km (seasonal) | 4 – 22 hours |

¹ Average figures, also based on tank size and average consumption


² Daily duty figure subject to route type (sites may operate the same bus on more than one route)

³ Planned operations ceased on 31st March 2014

Dramatic fuel economy improvements



- One of the most significant results of the trial program is the **improvement in the fuel economy: 8kg H₂/100km app. for the 12m buses (= ~ 27l diesel) = 30% more energy efficient than a diesel bus¹ and a >50% improvement compared with previous fuel cell bus generation (HyFLEET:CUTE)**
- Why? use of **fully hybridised powertrains, smaller and more optimised fuel cell systems**



¹ Assumption: fuel consumption of a diesel bus: 40 l of diesel/100km

- All European partners are able to fill a bus from empty **in less than 10 minutes** in average.

| City | Refuelling time | Station specification |
|---------------|-----------------|-----------------------|
| London | <10 minutes | 10 minutes |
| Aargau | <10 minutes | 10 minutes |
| Bolzano/Bozen | <10 minutes | 15 minutes |
| Oslo | <10 minutes | 10 minutes |
| Cologne | <10 minutes | 10 minutes |
| Hamburg | <10 minutes | 10 minutes |
| Whistler | 20 minutes | 10 minutes |

- Remaining concern around refuelling stations operation: **inability** of stations **to meter hydrogen supply accurately enough** (i.e. as for other conventional fuels)

High station availability



- The **availability** of stations in the CHIC project has been consistently **high**, with an average availability **over 95%** at most sites; the stations are well integrated in busy bus depots
- However, this figure is not high enough to allow hydrogen to satisfy a large share of a fleet

| | City | Availability to date (Aug. 2015) |
|---------|----------|----------------------------------|
| Phase 1 | Aargau | > 96% |
| | Bolzano | > 98% |
| | London | > 98% |
| | Milan | > 96% |
| | Oslo | > 94% |
| Phase 0 | Cologne | > 97% |
| | Hamburg | > 93% (since Aug. 2013: > 98%) |
| | Whistler | > 98% |


In Aberdeen
this figure is
over 99.8%
after two
years

- The 18-month EU project **NewBusFuel** started in summer 2015 to look at engineering solutions for depots integrating a larger fuel cell bus fleet (50-200 buses – 1,000-5000kg hydrogen/day in 12 locations across Europe)

Availability: After having faced teething issues, most of the Phase 1 cities are reaching the project target



- As is the case for all innovative technologies, one cannot expect a fuel cell bus to be 100% operational on day one, a teething period is necessary, during which lower availability is expected. This can be explained as the supply chain is still immature, and is expected to be solved with an increase in scale in the sector.
- It has to be noted that the most of the issues are not directly linked to the fuel cell
- An availability upgrade programme has been implemented in 2014 with positive results: **the availability in some cities exceed 90%, with an average >80% in the Phase 1 cities**



- Introduction
- Project status
- Emerging results – achievements and issues
- Conclusions
- Resolving the cost problems - Joint procurement project

Progress against targets – summary (end 2016)

| Application | Parameter | Unit | 2012 | FCH-JU target | | |
|--------------------------|--|-------------------------|--------|-------------------|--------------------|--------------------|
| | | | | 2017 | 2020 | 2023 |
| Fuel cell electric buses | Specific FC system cost | €/kW | < 3500 | < 1800 750 | 1000 500 | 800 400 |
| | FC Bus System Lifetime | hours | 10000 | 15000 2 x 8000 | 20000 2 x 10000 | 25000 2 x 12500 |
| | FC Bus cost | k€ | 1300 | 700 | 650 | 500 |
| | Fuel consumption (vehicle, average of SORT1 and SORT2 cycle) | kgH ₂ /100km | 9 | 8.51 | 8 | 7.59 |
| | Availability | % | 85 | 90 | 95 | 99 |
| | Assumed number of units (per year) as cost calculation basis | | | < 50 | 200 | > 500 |



Start of CHIC



Status today (end 2016)

Opportunities and next steps suggested by CHIC




- The CHIC project is demonstrating that **fuel cell buses have the potential to provide the same operational flexibility as conventional diesel buses**
- They can do this with **zero local emissions**, a contribution to transport decarbonisation and **satisfying the travelling public and the drivers**

Required next steps

- **Bus availability needs to improve** over 85% - *expected to be resolved by a) resolving the teething issues in the current trial and b) scale in the supply chain*
- **Bus prices need further reduction to enable genuine market traction** (less than €500,000) - *resolved through the FCH JU commercialisation process (see next slides)*
- **Regulations on hydrogen refueling stations construction and safety need to be further harmonised at EU and international level**— Key stakeholders are working *at European and international standards to simplify procedures and decrease costs*
- **Cost of hydrogen for buses needs to improve** – this requires attention to both bus efficiency AND low cost hydrogen at scale

CHIC brochure to be published next week



Final conference has become the Zero Emission Bus conference on 30th November to 1st December.

Over 200 attendees from around the world....


- Introduction
- Project status
- Emerging results – achievements and issues
- Conclusions
- Next steps – the JIVE project

The JIVE project will help commercialise fuel cell buses through a large-scale demonstration across five Member States

JIVE: Joint Initiative for hydrogen Vehicles across Europe

Objectives

- Deploy 142 FC buses across nine cities
- Achieve 30% cost reduction versus state of the art
- Operate 50% of the vehicles for at least 36 months
- Deploy the largest capacity HRS in Europe
- Achieve near 100% reliability of HRS
- Demonstrate technological readiness of FC buses and HRS
- Encourage further uptake



JIVE will be a six year project, with an anticipated start date of early 2017



Thank you for your attention


www.chic-project.eu

Email: h2businfo@chic-project.eu

Or ben.madden@element-energy.co.uk



NewBusFuel project



Inter-study partners: Element Energy, thinkstep, EvoBus